

**CITY OF HIALEAH
PALM CENTER PARKING GARAGE
265 PALM AVE
HIALEAH, FLORIDA**


June 9, 2010

TO ALL CONCERNED

The original Contract Documents for the Project entitled: **CITY OF HIALEAH – PALM CENTER PARKING GARAGE – STRUCTURAL PILES, BID NO. 2009/10-3230-00-085** is amended as noted in this Addendum No. 1.

This Addendum No. 1 consists of 1 Typed Page, 0 Sketches 1 Attachment and 0 Drawings. All other items and conditions of the original Contract Documents shall remain unchanged. This Addendum shall become a part of the Contract Documents.

Approved for issue: _____



Date: June 9, 2010

Oniel E. Toledo – Capital Project Manager
Construction & Maintenance

ACKNOWLEDGEMENT

Receipt of this **Addendum No. 1** shall be acknowledged in the space provided on the ADDENDUM RECEIPT FORM (ARF) (copy attached) now a part of the Contract Documents and to be faxed immediately to City of Hialeah @ (305) 687-2642 and submitted with sealed bids.

ATTACHMENTS:

ATT-1 **REVISED SUMMARY OF WORK (06/09/2010)**

STRUCTURAL PILES, BID NO. 2009/10-3230-00-085

**PAGE 1 OF 1
END OF ADDENDUM No. 1**

ADDENDUM RECEIPT FORM

**CITY OF HIALEAH
PALM CENTER PARKING GARAGE
STRUCTURAL PILES**

CONTRACTOR'S NAME _____

ADDRESS _____

PHONE NO. _____ **FAX NO.** _____

CONTACT NAME _____ **SIGNATURE** _____

THE BIDDER ACKNOWLEDGES RECEIPT OF THE FOLLOWING ADDENDUM BY SIGNING AND DATING BELOW: (COPY OF THIS FORM MUST BE FAXED AND IMMEDIATELY TO CITY OF HIALEAH @ (305) 687-2642

ADDENDUM

SIGNATURE

DATE

_____ 1 _____

PALM CENTER PARKING GARAGE

STRUCTURAL PILES

SUMMARY OF WORK

(Revised 06/09/2010)

Responsibilities of the pile contractor include all labor and material for the complete installation of the auger piles, but are not limited to:

- Contractor to auger 125 Ton, 14" Diameter, 7000 psi piles as noted on "structural" Drawings
- Furnish and install all pile reinforcing steel; including centering devices.
- City to provide survey layout; including pile locations, benchmarks, cut-off elevations, as built surveys and pile numbering.
- Furnish, erect and install test piles
- Remove load test frame and equipment
- Please note that contractor now must be allow to submit any additional cost if necessary for the excess grout if any.
- Pile contractor to chip piles to require length, after shell contractor has marked the piles and has prepared the site for pile caps.
- Remove earth spoil, excess grout and cut-off butts from job site
- Contractor to call for building inspections & perform needed testing (**City to provide testing company**)
- Provide all necessary equipment to perform work
- Follow safety guidelines and OSHA requirements
- Use proper safety gear at all times
- Debris removal (City will provide dumpster)

AT7-1