

ADDENDUM No. 23

**CITY OF HIALEAH
MILANDER AUDITORIUM
4800 PALM AVENUE
HIALEAH, FLORIDA**

FEBRUARY 10, 2011

TO ALL CONCERNED

The original Contract Documents for the Project entitled: **CITY OF HIALEAH – MILANDER AUDITORIUM – ELECTRICAL, BID NO. 2009/10-3230-00-093** is amended as noted in this Addendum **No. 23**.

This Addendum **No. 23** consists of **2** Typed Pages, **0** Sketches **0** Attachment and **0** Drawings. All other items and conditions of the original Contract Documents shall remain unchanged. This Addendum shall become a part of the Contract Documents.

Approved for issue:

Jorge Guanchez – Director

Date: February 10, 2011

ACKNOWLEDGEMENT

Receipt of this **Addendum No. 23** shall be acknowledged in the space provided on the **ADDENDUM RECEIPT FORM (ARF)** (copy attached) now a part of the Contract Documents and to be faxed immediately to City of Hialeah @ (305) 687-2642 and submitted with sealed bids.

CLARIFICATIONS:

1. The fire alarm system is not part of the electrical contractor' scope of work. It will be bid separately. Electrical contractor only needs to provide an independent 120 V circuit, for the fire alarm panel, to be located inside the electrical room.
2. The Key card system is also not part of the electrical contractor' scope of work. Electrical contractor only needs to provide an independent 120 V circuit, for the Key card panel, inside the audio/visual control room.

ADDENDUM No. 23

**CITY OF HIALEAH
MILANDER AUDITORIUM**

3. Contractor must provide 2-1.5" underground PVC pipes to each location noted below. Starting at the electrical room and ending at the outside of all four sides of the building on a pull box for future use.
 - a. North – grass area, North of restroom # 114
 - b. East – East of semicircular window at exhibit-gather area #102
 - c. South – grass area South of generator pad
 - d. West - Next to ramp entrance to summer camp room #119
4. All walkway lighting poles, labeled "P" (as shown on sheet E-8), are not part of this contract. Electrical contractor only needs to also provide, 1-1.5" PVC pipes for each circuit, starting at the electrical room and ending outside the building, at each location shown in the plans (noted on sheet E-8) terminating on a pull box.
5. **All piping inside the building must be metallic. MC cable is not acceptable.**
6. Install 2-2" PVC pipes for future computer system. From left side of elevator at audio/visual room to sod area North of restroom # 114
7. Contractor needs to install 2- 1.5" PVC pipes from the SE corner of the stage to the sound booth (to be placed in the planter area, behind the amphitheater steps. The sound booth will be approximately 5' X 7'. Contractor need to supply a 120V outlet, a ceiling light and a switch inside the booth. Also, a 120V GFI outlet behind the wall (exact location to be determined in the field).
8. Contractor need to install 2-2" PVC underground pipes for telephone & 2-2" for cable TV, both from the electrical room to a wooden pole at the SE corner of the property.
9. FPL transformer will now be placed 3', immediately West of the generator pad.

ADDENDUM RECEIPT FORM

**CITY OF HIALEAH
MILANDER AUDITORIUM
ELECTRICAL**

CONTRACTOR'S NAME _____

ADDRESS _____

PHONE NO. _____ **FAX NO.** _____

CONTACT NAME _____ **SIGNATURE** _____

THE BIDDER ACKNOWLEDGES RECEIPT OF THE FOLLOWING ADDENDUM BY SIGNING AND DATING BELOW: (COPY OF THIS FORM MUST BE FAXED AND IMMEDIATELY TO CITY OF HIALEAH @ (305) 687-2642

ADDENDUM

SIGNATURE

DATE

23

ARF