

**CITY OF HIALEAH
MILANDER - PARKING GARAGE
4840 PALM AVENUE
HIALEAH, FLORIDA**

DECEMBER 4, 2009

TO ALL CONCERNED

The original Contract Documents for the Project entitled: **CITY OF HIALEAH – MILANDER PARKING GARAGE – SECURITY FENCE, BID NO. 2009/10-3230-00-031** is amended as noted in this Addendum No. 2.

This Addendum No. 2 consists of 2 Typed Pages, 0 Sketches 1 Attachment and Drawings. All other items and conditions of the original Contract Documents shall remain unchanged. This Addendum shall become a part of the Contract Documents.

Approved for issue:  Date: December 4, 2009
Michael Flores – Purchasing Director

ACKNOWLEDGEMENT

Receipt of this **Addendum No. 2** shall be acknowledged in the space provided on the ADDENDUM RECEIPT FORM (ARF) (copy attached) now a part of the Contract Documents and to be faxed immediately to City of Hialeah @ (305) 687-2642 and submitted with sealed bids.

Questions and Answers

- Q1. Does the fence bid require any metal backing?
A1. No.
- Q2. What color is the fence?
A2. White.
- Q3. Are windows included in the bid?
A3. No.
- Q4. There is a drawing showing aluminum louvers, are they also to be included in the bid?
A4. No.
- Q5. Please specify the following:
If perimeter fence is aluminum or galvanized steel?
If handrails on the stairways will be aluminum or galvanized steel?
If is galvanized steel please specify finish color.
A5. See attached revised "Summary of Work".

**PAGE 1 OF 1
END OF ADDENDUM No. 2**

ADDENDUM RECEIPT FORM

**CITY OF HIALEAH
MILANDER PARKING GARAGE
SECURITY FENCE / RAILINGS**

CONTRACTOR'S NAME _____

ADDRESS _____

PHONE NO. _____ **FAX NO.** _____

CONTACT NAME _____ **SIGNATURE** _____

THE BIDDER ACKNOWLEDGES RECEIPT OF THE FOLLOWING ADDENDUM BY SIGNING AND DATING BELOW: (COPY OF THIS FORM MUST BE FAXED AND IMMEDIATELY TO CITY of HIALEAH @ (305) 687-2642

ADDENDUM

SIGNATURE

DATE

2

ARF

CITY of HIALEAH

HIALEAH HIGH PARKING GARAGE

SECURITY FENCING

SUMMARY OF WORK (revised)

Responsibilities of the Metal Railing Contractor include the complete security fencing system of the 1st floor perimeter and stairs as per plans and specifications including but not limited to:

- Shop Drawings and Submittals
- Supply and Install all metal fencing for garage
- Supply and Install all metal railings for handrails
- All railings shall be powder coat painted.
- All fencing shall be *powder coat* painted
- No welding on site.
- Grind all welds and any imperfections from finished product before painting
- No Electrostatic painting.
- Fabricate and Install all miscellaneous metals
- Touch up all metal fencing
- Properly sealed poles perforations to avoid future water accumulation
- The intent is to have fence panels installed on all first floor and ramp to second floor openings on the west side.
- The maximum post spacing will be no more than 6'4". In some occasions contractor may have to adjust or spread evenly accordingly to the space available.
- All fencing will need to have the top and bottom rail minimum and then provide necessary intermediate rails accordingly to space, to form a square pattern.
- The posts size has to be 2" x 4" x 1/4".
- The posts have to have a 4" x 6" plate welded at the ends, with four (4) holes for 1/4" x 3 1/4" "tapcon"
- The fence sections have to be secured to the side walls.
- The top of each panel can be secured to the underside of the horizontal post tensioned beams.
- For anchoring please use 4- 1/4" x 3 1/4" "tapcon" at each end of poles.
- The fence needs to be painted white (powder coated).
- The wind load calculation and the shop drawings for the railings and fence need to be provided by fencing contractor prior to manufacture and installation of the fence.
- Install all fencing and railings as per ADA (Handicap code)
- Use OSHA certified equipment
- Supply all Labor and Equipment to perform work including delivery and distribution of materials
- Clean up and Debris removal
- Cutting and Patching

**** All stair handrails and metal fencing shall be made of aluminum.****